


P: 866.733.0233 www.solerpalaucanada.com

OPTIONS:

- 1. Insulation retainers solid or screen type.
- 2. Burglar bars 1/2" dia. on 6" centers.
- 3. Finishes baked or air-dried enamel or epoxy.
- 4. Heights: 8, 12, or 16".
- 5. Single pitch, double pitch or flat style.
- 6. Damper Tray.



	"A" OD (Square) CURB / RF TYPE											
FAN SIZE	CENT. SUPPLY (KSF)	CENT. SUPPLY (CSF, LSF)	CENT. SUP- PLY (SRT)	UP- BLAST ROOF (UBB, UBS, UBX, UBRD)	UPBLAST ROOF (UBSRD, UBSRD-HT, UBSRD- HT1)	UP- BLAST ROOF (TUB, TUB-HT)	HOODED ROOF (HREB-C, HRSB, HRED-C, HRSD, HRSBF, HRSDF)	PRO- PELLER ROOF (ARE/ ARS)	"B" CURB HEIGHT	"C" WOOD NAILER	GAUG- ES	WT.
9	22-1/4	22-3/4	-	-	-	-	-	-				34
10	26-1/2	26-1/2	14-3/4	-	-	-	-	18-1/2				36
12	30-1/2	26-1/2	-	-	-	-	-	22-1/2				36
15	30-1/2	30-1/2	-	-	-	-	-	-				36
16	-	-	-	-	-	-	-	26-1/2				36
18	34-5/8	34-5/8	-	-	-	-	-	-				40
20	49	49	-	-	-	-	-	30-1/2	12"	1-1/2"	18	58
24	-	-	-	31	28-1/2	33-1/4	33-1/4	-	STD	Sq	10	39
30	-	-	-	37	34-1/2	39-1/4	39-1/4	-				46
36	-	-	-	43	40-1/2	45-1/4	45-1/4	-				54
42	-	-	-	49	46-1/2	51-1/4	51-1/4	-				61
48	-	-	-	55	52-1/2	57-1/4	57-1/4	-				68
54	-	-	-	61	58-1/2	63-1/4	63-1/4	-				75
60	-	-	-	67	64-1/2	69-1/4	69-1/4	-				82

- 1. Standard construction is shown. If special construction is required, note changes below and highlight.
- 2. G-90 galvanized welded steel construction.

ACCESSORY ITEMS	1	2	3	4	5	ACCESSORY ITEMS	1	2	3	4	5

Project:	Submitted:
Customer:	Approved:
Location:	PP




MAGNETIC DAMPER LATCH INSTALLATION INSTRUCTIONS

PARTS REQUIRED

- 2 Magnetic Latches
- 2 2" x 4" Strike Plates
- 16 #10 Self Tapping Screws
- 1. Locate latches as shown.
- 2. Attach magnet to wind band with 4 #10 self tapping screws.
- 3. Attach 2" X 4" latch plate to bottom of damper doors (required on fiberglass doors) with 4 #10 self tapping screws, making sure it makes contact with magnets on latch.
- 4. Make sure latch is level and true with damper for good holding power select smooth & level damper area for installation.
- 5. Caulk around all screws on damper doors to eliminate leakage.

CHECK OPERATION MANUALLY



SIDE VIEW

